

REQUEST FOR QUOTES:

Helga Township is requesting quotes for topdressing select aggregate roads this spring (see attached exhibit). The total quantity of aggregate required is estimated at 3,000 CY and must be placed prior to Hubbard County’s application of chloride. The selected contractor is expected to coordinate with the Township to schedule placement of aggregate. Work may begin as soon as road restrictions lift with all aggregate placed by Thursday, June 12, 2025..

Scope of work:

The selected contractor will be responsible for applying water to the roads prior to placing aggregate (incidental to aggregate), then placing aggregate ahead of grader adequate to provide approximately 2” of loose material (packed to 1-1/2”). Helga Township will provide a road grader and staff to grade and compact material after it is placed. The contractor shall provide production gradations of material meeting the specifications.

Payment:

Payment will be made based on the actual quantity placed, loose volume (LV) up to the total estimated quantity. The contractor will be responsible for providing load slips, tracking quantities and submitting pay requests to Township for approval. No material placed over the total estimated amount will be reimbursed without written authorization from the Township. The contractor is responsible for monitoring quantities and shall notify the Assistant Road Supervisor if quantities appear to be tracking over estimate so that remedial actions can be made.

Please provide a quote for estimated work based on the following quantities:

MnDOT SPEC NO	ITEM DESC	EST QTY	UNITS	UNIT COST	TOTAL EST COST
2118.507	Aggregate Surfacing (LV), Class 1	3,000	CU YDS		

Along with a quote, please provide a location of the proposed gravel pit/pile and be aware the Township may request to visit the site and/or have the contractor provide a material sample.

Location of pit/pile: _____

Questions: Contact Keith Kinnen at 218-841-3755

Please submit quotes no later than **Thursday May 15th, 2025 @ 5:00 pm**

PLEASE SUBMIT QUOTES TO:

keith@helgatownship.com

-or-

Keith Kinnen, Road Supervisor
22943 County 9
Bemidji MN 56601

Attachments:

Gravel Location Exhibit

Total Chloride Required: 11.70 Miles
Total Gravel Required: 3.15 Miles

LEGEND

- FEDERAL STATE
- COUNTY STATE AID HWY
- COUNTY ROAD
- TOWNSHIP ROAD
- MINIMUM MAINTENANCE
- LOCAL ROAD
- BIKE TRAIL

TOWNSHIP MILEAGE → 28.74

- STATE FOREST
- GAME REFUGE
- NATIVE AMERICAN RESERVATION

INCORPORATED CITY Unincorporated

- PUBLIC ACCESS
- TOWN OR TOWNSHIP HALL
- BRIDGE OR BOX CULVERT

APPROXIMATE SCALE
 1 MILE

HUBBARD COUNTY
 HIGHWAY DEPARTMENT
 REVISED - NOVEMBER 30, 2022

